

208Y/120 VOLT, THREE-WIRE & FOUR-WIRE PRE-ASSEMBLED MODULAR METERING INSTALLATION WHERE A MAIN DISCONNECTING MEANS IS REQUIRED ON THE SUPPLY SIDE OF THE METERING EQUIPMENT (SEE NEC) (200 AMPERES MAXIMUM)

PRE-ASSEMBLED MODULAR METERING UNITS MUST BE APPROVED BY THE COMPANY PRIOR TO INSTALLATION
CONTACT POWER DELIVERY FOR INFORMATION REGARDING ACCEPTABLE UNITS OR THE APPROVAL PROCEDURE

